

GENERAL FIRE ALARM NOTES REQUIRED ON DRAWINGS

FIRE ALARM SYSTEMS

All Fire Alarm Systems shall be installed in accordance with applicable provisions of NFPA, Fire Code, Building Code and ANSI Standards.

One set of approved drawings shall be maintained on-site and made available to City Inspectors on demand.

A City Inspector shall witness the final acceptance test of the alarm system. Call 480-782-3100 to schedule an appointment at least 72 hours in advance.

A contractor licensed to perform such work shall install fire protection systems by the State of Arizona, and who also is on the Chandler Fire Department Contractors List for such work.

Electrically operated water flow alarm devices attached to sprinkler systems to provide required supervision shall be interconnected to the fire alarm system in accordance with the appropriate NFPA standard.

Alarm system supervision of sprinkler system trouble and water flow indications in buildings more than one story high, shall be provided by the fire alarm system in accordance with NFPA 13.

The contractor shall provide the City Inspector two copies of a "Fire Alarm System Certification and Description" record, with Section 1 and Sections 3 through 9 fully filled out, prior to the start of the final acceptance test. One copy of the completed form will then be given to the contractor upon successful completion of the test.

The contractor is to place a floor plan of the building inside the Fire Alarm Panel. The floor plan shall show the location of all devices and provide room numbers and/or description of room that is compatible with the Fire Alarm System notification (example: 1st floor smoke detector room 103 or break room).

*Zone Maps are to be placed in the Fire Alarm Panel.

The contractor shall place a key to the fire alarm panel in the Key Box.

All Fire Alarm Rooms shall be signed in accordance with Fire Department detail FD106.